



Quench 575-CT Pre-Installation Checklist

Thank you for being a Quench customer! We are excited for your workplace to experience the great-tasting sparkling water from your new Quench 575-CT. Before our certified technician can install your machine, the following pre-installation requirements must be completed.

Water Supply

- ◆ 1/2" potable water supply line terminating in 1/2" ball valve with 1/2" female pipe thread to connect to (ball valve must be accessible for service and installation)
- ◆ Minimum water supply pressure 50 PSI, 1.3 gallon per minute minimum flowrate
 - ◆ Must be a dedicated 1/2" water supply line with no other connections
 - ◆ Any water line or valve less than 1/2" is not acceptable
- ◆ Water ball valve must be located at low level with sufficient room for 12" long fitting to be connected to the ball valve

Electrical

- ◆ Dedicated 120 VAC/60Hz/15 amp (NEMA 5-15 receptacle) electrical circuit
- ◆ Electrical connections within 40" of machine location; **NO EXTENSION CORDS**

Countertop Placement

- ◆ 1" diameter hole for the water line and CO₂ line to the Quench 575-CT
 - ◆ Quench technicians are only permitted to drill through laminate or Corian counters. Any other surface must be pre-drilled prior to install.

Ventilation

- ◆ Water shut-off valve must be located at low level with sufficient room for a 12" long fitting to be connected to the shut-off valve.
- ◆ If installed in an enclosed space, adequate ventilation must be provided.

CO₂ Supply

- ◆ CO₂ cylinder is on-site
 - ◆ If connecting to a bulk or existing CO₂ system, a CO₂ line terminating at 1/4" barbed shutoff valve must be available within 40" of the installation site
 - ◆ Minimum CO₂ pressure is 100 PSI

**If you have any questions about the installation requirements,
call Customer Care at 888-554-2782!**

